BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

75

NEGOTIATED SCHEDULE - B

Issued to

Tender Number BBMP/2016-17/BD/WORK_INDENT21513
Tender Name Construction of Additional Class rooms, toilet and Auditorium and

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
1	FIRST FLOOR Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work B. In cement mortar. with all lead and lifts and directions of the Engineer-In-Charge of the work.	Cum	17.07	275.00	Rupees Two Hundred Seventy Five only
2	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	66.96	420.00	Rupees Four Hundred Twenty only..
3	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	164.67	427.00	Rupees Four Hundred Twenty Seven only

A. Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
10	Providing and removing centering, shuttering, strutting, propping etc., for chajjas,corbels etc.,including edges including cost of all materials labour complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	20.25	318.00	Rupees Three Hundred Eighteen only.
11	Providing and laying in position reinforced cementconcrete of design mix M20 with OPC cement @ 24kgs, with 12mmand down size graded granite metal coarse aggregates @0.5175cumand fine aggregtes @ 0.345cum, with superplastisiser @0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. averagethickness, upto ground floor level, including cost of all materials, labour,HOM of machinery, finishing, curing, complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	20.25	500.00	Rupees Five Hundred only
12	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	M.T	11.15	74,900.00	Rupees Seventy Four Thousand Nine Hundred only.
13	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqmm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x20x20 cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	404.91	1200.00	Rupees one Thousand Two Hundred only.
14	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	381.46	246.00	Two Hundred Forty Six only

74

A. Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
20	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Kgs	1063.13	130.00	one Hundred Thirty only
21	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium	Sqm	50.63	4900.00	Rupees Four Thousand Nine Hundred only
22	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	406.71	1400.00	Rupees one Thousand Four Hundred only
23	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	885.62	60.00	Rupees Sixty only

A Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
30	Providing and laying in positon plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregrates @ 0.69cum and fine aggregates @ 0.43cum,with super plastisiser @ 3 litres confirming to IS 9103-1999 reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15 cms thick will compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	33.48	6500.00	Rupees Six Thousand Five Hundred only
31	Extra for use of water proofing compound in cement concrete of mix M-20, @ 1kg of compound per Bag of cement. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	33.48	220.00	Rupees Two Hundred Twenty only
32	Fixtures Providing and fixing of Door locking arrangements with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	5.00	700.00	Rupees Seven Hundred only
33	Providing and fixing of Handles powder coated 150mm with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	5.00	60.00	Rupees Sixty only
34	Providing and fixing of Hinges 5" heavy duty with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	50.00	40.00	Rupees Forty only
35	Providing and fixing of Hold fasts MS with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	10.00	40.00	Rupees Forty only
36	Providing and fixing of Tower bolt 300mm long. with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	15.00	120.00	Rupees one Hundred Forty only
37	STAIRCASE AND TOILET BLOCK Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	5.88	380.00	Rupees Three Hundred Eighty only
38	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work B. In cement mortar. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	84.87	260.00	Rupees Two Hundred Sixty only

A. Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

5/7

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
45	Transportation of excavated earth by mechanical means including loading and unloading with a lead of 20 kmtr and dispersing the same as directed. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	78.28	128.00	Rupees one Hundred Twenty Eight only
46	Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs ,with 40mm and down size graded granite metal coarse aggregates @ 0 .892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials,labour, HOM of machinery ,curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	15.68	6000.00	Rupees Six Thousand only
47	Providing and constructing granite / trap / basalt Size Stone Masonry in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of maerials, labour, curing Complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	26.51	4500.00	Rupees Four Thousand Five Hundred only
48	Providing and laying in position reinforced cement concrete of design mix M25 with OPCcement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cumn and fine aggregtes@ 0.47cum, with superplastisiser @3lts confirmingto IS9103-1999 reaffirmed 2008,machine mixed, concrete laid in layersnot exceeding 15 cms thick, vibrated for all work in foundation for fooiings,pedestals, retainingwalls, return walls, walls(any thickness) including attached plasters,columns, pillars, posts, struts, buttresses, bed blocks, anchor blocks, and plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	17.51	7000.00	Rupees Seven thousand only

A Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
53	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	61.62	380.00	Rupees Three Hundred Eighty only
54	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	63.18	400.00	Rupees Four Hundred only
55	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.50 m from Ground level. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	200.46	360.00	Rupees Three Hundred Sixty only
56	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and likes thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.50 m from Ground level. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	172.26	350.00	Rupees Three Hundred Fifty only
57	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	49.39	280.00	Rupees Two Hundred Eighty only
58	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	39.19	280.00	Rupees Two Hundred Eighty only
59	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour completeas per specificaiton. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	27.80	550.00	Rupees Five Hundred Fifty only

A. Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
65	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	67.20	800.00	Rupees Eight Hundred only
66	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size 40x10x20cms confirming to I.S 2185/1965 in Super structure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	33.60	800.00	Rupees Eight Hundred only
67	Providing 12mm thick cement plaster in single coat with cement mortar 1:3 to Ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	327.74	246.00	Rupees Two Hundred Forty Six only
68	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	386.47	260.00	Rupees Two Hundred Sixty only
69	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	241.30	270.00	Rupees Two Hundred Seventy only

A Gangulu Reddy

Signature of the Contractor

5/7

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
75	Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	151.41	1650.00	Rupees one Thousand Six Hundred Fifty only
76	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications. B731. Ground Floor. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	24.00	1100.00	Rupees one Thousand one Hundred only
77	Providing Honne Wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	1.82	1,10,000.00	Rupees one Lakh Ten Thousand only
78	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	36.48	4900.00	Rupees Four Thousand Nine Hundred only
79	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	18.24	4900.00	Rupees Four Thousand Nine Hundred only

A Gangadeva Reddy

Signature of the Contractor

5/7

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
83	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame,stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium	Sqm	6.03	4500.00	Rupees Four Thousand Five Hundred only
84	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications.(Staircase) Ground Floor.with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	93.33	1300.00	Rupees one Thousand Three Hundred only
85	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed withcement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications.(Staircase) First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	93.33	1300.00	Rupees one Thousand Three Hundred only
86	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	955.51	64.00	Rupees Sixty Four only

A Gangulu Reddy

Signature of the Contractor

5/7

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
92	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	137.50	90.00	Rupees Ninety only
93	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as perspecifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	38.68	90.00	Rupees Ninety only
94	Providing and laying in positon plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregrates @ 0.69cum and fine aggregates @ 0.43cum,with super plastisiser @ 3 litres confirming to IS 9103-1999 reaffirmed-2008, machine mixed concrete laid in layers not exceeding 15 cms thick will compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	15.03	6500.00	Rupees Six Thousand Five Hundred only
95	Extra for use of water proofing compound in cement concrete of mix M-20, @ 1kg of compound per Bag of cement. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	15.03	224.00	Rupees Two Hundred Twenty Four only
96	Fixtures Providing and fixing of Door locking arrangements with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	5.00	700.00	Rupees Seven Hundred only
97	Providing and fixing of Handles powder coated 150mm with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	5.00	63.00	Rupees Sixty Three only
98	Providing and fixing of Hinges 5" heavy duty with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	50.00	40.00	Rupees Forty only
99	Providing and fixing of Hold fasts MS with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	10.00	40.00	Rupees Forty only
100	Providing and fixing of Tower bolt 300mm long with all lead and lifts and directions of the Engineer-In-Charge of the work	Each	15.00	130.00	Rupees one Hundred Thirty only

A. Ganguly Reddy

Signature of the Contractor

Executive Engineer (Project)

Sl No	Item Name	Unit	Estimate Quantity	Negotiated Rates quoted by Sri GANGULU REDDY A	
				Rate in figures	Rate in words
106	KSRB 4.9.2 Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work	M.T	2.24	59,150.00	Rupees Fifty Nine Thousand one Hundred Fifty only
107	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing curing complete as per specification and Extra for providing and mixing waterproofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:3, 12mm thick cost of materials complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	32.00	220.00	Rupees Two Hundred Twenty only
108	Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherver required smooth rendering, Providing and removing scaffolding, cost of materials, labour, curing complete as per specification and Extra for providing and mixing waterproofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:4, 18mm thick cost of materials complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	Sqm	27.72	280.00	Rupees Two Hundred Eighty only
109	Providing and fixing square tank covers of size 24x24 with all lead and lifts and directions of the Engineer-In-Charge of the work	No	1.00	1400.00	Rupees one Thousand Four Hundred only
110	Providing 20mm square M.S.Footrest and fixing in manhole with 1:3:6 cement concrete block of 20x20x10 cms using 20mm an ddown size metal of size including cost of materials, labour charges, curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work	No	4.00	300.00	Rupees Three Hundred only
111	Transportation of excavated earth by mechanical means including loading and unloading with a lead of 20 kmtr and dispersing the same as directed. with all lead and lifts and directions of the Engineer-In-Charge of the work	Cum	38.83	120.00	Rupees One Hundred Twenty only

A. Gangulu Reddy

Signature of the Contractor

Executive Engineer (Project)